BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT14674

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Improvements to roads and drains in Amruthanagar A Sector in Ward no.07, Byatarayanapura, Kodigehalli sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B RAMAMOHANREDDY	
				In Figures	In Words
1	3601	Removing BS Slab of drain and stacking.	Sqm	57.74	Rupees Fifty Seven and Seventy Four Paise Only
2	2880.8	Refixing stone slabs of drains and pointing in CM 1:3.	Sqm	74.84	Rupees Seventy Four and Eighty Four Paise Only
3	720.2	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick)	Sqm	632.97	Rupees Six Hundred Thirty Two and Ninety Seven Paise Only
4	1135.15	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.	cum	74.84	Rupees Seventy Four and Eighty Four Paise Only
5	17.1	KSRB - 4-1.6: Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5274.36	Rupees Five Thousand Two Hundred Seventy Four and Thirty Six Paise Only
6	332.8	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc, and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications. Specification No KBS 4.6.2. (Page No.15 item No.4.30) SR 2014-15	Sqm	380.64	Rupees Three Hundred Eighty and Sixty Four Paise Only
7	10.8	KSRB - 5.2.3: Providing and constructing granite size stone masornry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m.apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	cum	3641.70	Rupees Three Thousand Six Hundred Forty One and Seventy Paise Only
8	52.24	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC Works laid in 15cms thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3 with all lead and lift etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns Staircase and Roof with M-20 (1:1.5:3) (Cement 320kg/cum) (Page No.18 item No.4.49.1) SR 2014-15	cum	5788.65	Rupees Five Thousand Seven Hundred Eighty Eight and Sixty Five Paise Only

Executive Engineer
Byatarayanapura Divn.
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

9	2.47	KSRB 4.9.2: Providing TMT. Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, lobour, HOM of machinery complete as per specifications. (Page No. 17 item No.4.46) SR 2014-15	Qtl	77568.32	Rupees Seventy Seven Thousand Five Hundred Sixty Eight and Thirty Two Paise Only
10	13459	KSRRB 300-44 Scarifying top bituminous surface or surface dressing or premix carpet including picking up scarified materials, stacking of old serviceable materials within a lead of 100 metres by manual means including cost of all abour charges complete as per specifications. MORTH Chapter 3 (P-143 I-19.50 SR-2014-15)	Sqm	22.45	Rupees Twenty Two and Forty Five Paise Only
11	13459	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications.	Sqm	4.44	Rupees Four and Forty Four Paise Only
12	1061.08	KSRRB 300-64.2. Extra for watering the earth to bring the earth upto required optimum moisture content with mechinery including cost of all labour, HOM of machineries complete as per specifications.MORTH Chapter 3 (P-146, I-19.72 SR-14-15	cum	2.14	Rupees Two and Fourteen Paise Only
13	2716	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 154, Item No. 20.18) SR 14-15	cum	1424.17	Rupees One Thousand Four Hundred Twenty Four and Seventeen Paise Only
14	14000	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 171, Item No. 21.6) SR 14-15	Sqm	39.24	Rupees Thirty Nine and Twenty Four Paise Only
15	354.55	KSRRB M500-18. Providing and laying semi dense bituminous concrete 25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 159, Item No. 21.20.5 SR-14-15	cum	8809.14	Rupees Eight Thousand Eight Hundred Nine and Fourteen Paise Only
16	1135.15	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	71.98	Rupees Seventy One and Ninety Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92